

ADDENDUM NO. 1 - QUESTIONS & ANSWERS

1/21/25

The subject Request for Proposal (RFP) is hereby amended per this Addendum No. 1, and the following questions and answers are provided as shown below. All other requirements of the RFP remain as originally stated. **Your proposal must acknowledge receipt of this Addendum.**

- 1) Can the quantity of the Primary Drain Rock (WOXSC1200 and WOXSC2010) and operations layer (WOXSC1220) be provided so an accurate testing quantity be determined?

Answer: Primary drain rock ~ 18,000 CY, Operations Layer ~ 82,000 CY, and Leachate Drainage Gravel ~ 275CY. This can be reference in the added attachment #13 in the RFP Instructions, Section B.

- 2) The SOW, Section 3.1 states, “Personnel must secure all necessary registrations, medical exams, bioassay evaluations, appropriate dosimeters and training required prior to performing any on-site work.” Will CPCCo provide the any site related medical exams, bioassay evals, dosimetry and site-specific training? Or will the CQA contractor be responsible to obtain these site-specific items?

Answer: The SOW, Section 5.2 states, “CPCCo will provide Contractor personnel task or facility specific training as required for site and facility access and safe performance of assigned tasks. Contractor shall maintain training records for their personnel. EJTAs, Medical Clearances and a full Training Record submittal are required if the Contractor hires new personnel to perform this Task. All required permits will be provided by CPCCo. The Contractor shall comply with and maintain a copy of all permits required by this SOW or the CQA BTR on the work site shall be able to display a copy of the permit(s) when requested (e.g., Hot Work Permit, Radiological Work Permit, Excavation Permit, etc.) All required permits will be provided by CPCCo. The Contractor shall comply with and maintain a copy of all permit(s) required by this SOW or on the work site and display a copy of the permit(s) when requested (e.g. Hot Work Permit, Radiological Work Permit, etc.)”

- 3) Relating to the required as-builts, the SOW specifies the Construction Contractor is responsible for the as built survey. The survey will be submitted to CPCCo, then CPCCo will submit the survey to the CQA Contractor. What is the required timing of submittal of the as built survey from the Construction Contractor to CPCCo? This

CONSTRUCTION QUALITY ASSURANCE FOR ERDF
SUPERCELL 11

ADDENDUM NO. 1 - QUESTIONS & ANSWERS

may affect the CQA contractors' ability to satisfy the submittal timeframes shown in the SOW Table 6.

Answer: The as built survey of the cell excavation is requested 10 days following completion of the survey. The intermediate surveying of the liner system (admix, drain rock, Operational layer) is not necessarily specified; it is the Construction Contractors best interest to submit early such that they are authorized to proceed to the next layer. CPCCo will work with the Contractor to ensure submittal preparation durations and review times are managed to support the best needs of the project.

- 4) The SOW and Technical Specifications indicate the contractor is responsible for soil field density testing. Will there be a conflict if the construction contractor and CQA contractor both subcontract portions of field testing and laboratory testing to the same 3rd party company? If this is a conflict will either contractor be allowed to revise their bid to utilize a separate vendor?

Answer: This will not be a conflict as long as the testing agency pulls separate samples; the field-testing agency will not be permitted to provide the results from one sample to both entities. The Construction Contractor and the CQA Contractor will be independently responsible for validating the testing agency's QA program and validity of the results to ensure the specifications and requirements of the contract are met.

- 5) The pricing proposal template Pay Items #7 and #8 list references 4.11 and 4.12 respectively. Are the references intended to be 4.1.1 and 4.1.2 respectively?

Answer: Correct – Should read 4.1.1 and 4.1.2. The attachment has been revised.