

1. Clarification to Q&A #01 in amendment 01, With Leak holes being required will a fusion bonded repair saddles be required? **Yes, leak holes must be closed after leak test**
2. Clarification to Q&A #02 in amendment 01, Hydro testing is only required for DWHDPE correct? **All pipe shall be leak tested**
3. Clarification to Q&A #11 in amendment 01, All lines will have DWHDPE? **For short portions, yes, except YE46 which is entirely DWHDPE**
4. Clarification to Q&A #13 in amendment 01, All lines cross a water line and will require 1ea. 40' stick over the water line? **See #5 below**
5. Will any wells require to cross multiple water lines?
 - a. **YE11: two crossings**
 - b. **YE39: two crossings**
 - c. **YE40: three crossings**
 - d. **YE41: one crossing**
 - e. **YE42: two crossings**
 - f. **YE43: two crossings**
 - g. **YE46: four crossing**
6. Clarification to Q&A #14 in amendment 01, Will any HDPE lines be tied in to a well or building? **None will be tied into a well; YE40 and YE43 will punch into ETB-2 and be flanged off; YE41 will punch into ETB-1 and be flanged off**
7. Clarification to Q&A #17 in amendment 01, Data logger to be used only on DWHDPE not HDPE? **Data logger shall be used for all fusion bonds on both HDPE and DWHDPE per Randall (Randy) Hallum**
8. Attachment B, How many signs will be required? Are these metal signs and attached to a Tee-Post? **3 signs will be required; 1 at YE46 wellhead, 1 on either side of road crossing 39 east of YE46 and south of U-Plant; signs should be double sided so they can be read from either side**